

<b>PROJECT:</b>	PROPOSED RENOVATION PLAY SCHOOL BUILDI	DATE-	06/06/2023		
<b>SITE :</b>	AT KARAD DIST: SATARA				
<b>CLIENT :</b>	SUPERINTENDENT OF POLICE SATARA				
<b>ESTIMATE</b>	BLOCK ESTIMATE				
<b>JOB NO:</b>	0733-A				
<b>A B S T R A C T</b>					
<b>Sr No</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
A	PLAY SCHOOL RENOVATION WORK				
	<b>Civil Work</b>				
1	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:4 in half brick thick wall including mild steel longitudinal reinforcement of 2 bars of 6 mm diameter / 2 hoop iron strips 25 mm X 1.6 mm placed at every third course, properly bent and bonded at ends scaffolding, racking out joints and watering etc. complete.	Sqmt	25.00		
2	Providing and laying vitrified mirror / glossy finish tiles decorative type having size 590 mm to 605 mm x 590 mm to 605 mm of 8 to 10 mm thickness and confirming to IS. 15622-2006 ( group Bla) of approved make, shade and pattern for flooring in required position laid on a bed of 1:4 cement mortar including neat cement float, filling joints, curing and clearing etc. complete.	Sqmt	50.05		
	Cost For the Portion of Civil Work of Renovation				
	Electrification (11%)				
	<b>Cost For the Portion of Civil Work of Renovation</b>				
	Add GST (18%)				
	Add consultancy charges (2%)				
	<b>Total Cost of Portion of renovation work</b>				

<b>PROJECT:</b>	PROPOSED RENOVATION PLAY SCHOOL BUIL			DATE- 06/06/2023	
<b>SITE :</b>	AT KARAD DIST: SATARA				
<b>CLIENT :</b>	SUPERINTENDENT OF POLICE SATARA				
<b>ESTIMATE</b>	BLOCK ESTIMATE				
<b>JOB NO:</b>	0733-A				
<b>A B S T R A C T</b>					
<b>Sr No</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
A	PLAY SCHOOL RENOVATION WORK				
1	Providing and fixing Toughened clear / colour Glass wall / partition Including heavy / jumbo anodised Alluminium / S.S. fittings , with pure Anodised colour coated sections including 12mm tk Imported Reflective toughened Glass fixing with both side Adhesive tape & 995 Silicon Sealent And grooves filling with 789 exterior grade Silicon Sealent (Fixing with nettel fold's screw's 'L' Bracket's fastern's as per requirements.) & Including all necessary fixtures and fastening, bearing, handles, door stopper, etc. as per detailed drawing and including necessary Scaffolding. Spec. : As directed by Architect/Engineer-in-charge	Sqm	42.00		
2	Providing and fixing sliding folding Auccoustical Partition with Rail on TOP of INOX Branded as per the details etc.	sqm	10.00		
3	Providing and fixing Dpi lux trnsulent pycarbonate sheet	Sqm	27.00		
4	Landscaping work	LS	1.00		
Cost For the Portion of Civil Work of Renovation					
Electrification (11%)					
<b>Cost For the Portion of Civil Work of Renovation</b>					
Add GST (18%)					
Add consultancy charges (2%)					
<b>Total Cost of Portion of renovation work</b>					